



5.5-9 The beam shown in [Figure P5.5-9](#) is a W36 x 182 (W920 x 271). It is laterally supported at A and B. The 300 kip (1,335 kN) load is a service live load. Using the unfactored service loads,

- a. Compute C_b . Do not include the beam weight in the loading.
- b. Compute C_b . Include the beam weight in the loading.




$$M_{MAX} = \frac{PL}{4} = \frac{300k(20ft)}{4} = 1,500 kft$$



$$M_A = 750k \cdot ft = M_C \quad M_B = M_{MAX}$$

$$C_b = \frac{12.5 M_{max}}{2.5 M_{max} + 3 M_A + 4 M_B + 3 M_C}$$

$$= \frac{12.5(1,500)}{2.5(1,500) + 3(750) + 4(1,500) + 3(750)} = \underline{\underline{1.316}}$$



$$M_{\max} = 1,500 + 9.10 = 1,509.1 \text{ kft}$$

$$M_A = 750 + 6.83 = 756.83 \text{ kft}$$

$$M_B = 1,500 + 9.10 = 1,509.1 \text{ kft}$$

$$M_C = 750 + 6.83 = 756.83 \text{ kft}$$

$$C_b = \frac{12.5(1509)}{2.5(1509) + 3(756.8) + 4(1509) + 3(756.8)} = \underline{\underline{1.315}}$$